


REFER TO DRAWING DB1B AC-S02 FOR CONTINUATION

NOTE:
ALL SEWER MAN LINES CONSTRUCTED AS PART OF STAGE 1B WORKS
HOUSE CONNECTION DETAILS FOR LOTS 36 AND 50 ARE NOT PART
OF THIS APPLICATION



- NOTES:-**
1. ALL SEWERS ARE 150 UPVC S88 UNLESS NOTED OTHERWISE
 2. ALL MANHOLE COVERS ARE CIRCULAR CONCRETE INFILL STAMPED SANSEW UNLESS NOTED OTHERWISE
 3. MANHOLE DROPS ARE TYPE 'A' UNLESS NOTED OTHERWISE (250mm MAX)
 4. ALL HOUSE CONNECTIONS SANSEW UNLESS NOTED OTHERWISE

AS CONSTRUCTED



I, Neville H Volker, hereby certify that the horizontal and vertical locations, and dimensions shown on this plan are a true and correct record of the AS Constructed information

OW / 371 / 2018

Project Name: Davidsons at Belivah - Stage 1D
Company: BELIVAH PTY. LTD.
Consultant: NH Volker & Co Pty Ltd
Reg No: 2753

Signature: *NH Volker* Date: 17/06/2019

APPROVED	AB / RMM	DATE	06/19
DWG. NO.	DB1D-AC-S01	REVISION	A

NH Volker
M. Reg. No. 4471
Grad. Dip. U.R.P.
Professional Surveyor
Email: nvolker@bigpond.net.au
Mbl. Phone 0411 759 765

Associated Consultant
PREMISE ENGINEERING PTY. LTD
LEVEL 1, 100 BRUNSWICK STREET
P.O. Box 361
FORTITUDE VALLEY QLD 4006

CLIENT
PLANLEX PTY. LTD.
P O Box 411
BEEBLEIGH QLD 4207
Email - nvolker@bigpond.net

PROJECT
DAVIDSONS at BELIVAH
STAGE 1D
Belivah Road, BELIVAH

DRAWING
AS CONSTRUCTED SEWERAGE
RETICULATION AND HOUSE CONNECTION
PLAN - STAGE 1D

APPROVED	AB / RMM	DATE	06/19
DWG. NO.	DB1D-AC-S01	REVISION	A

COUNCIL Ref. No. - OW/371/2018